# Genesee County Land Bank Authority Blight Elimination Program Request for Proposals- LB 18-005 Environmental Abatement, Demolition and Restoration of 810 S Ballenger Hwy ADDENDUM #1

#### March 30, 2018

The following information is to be incorporated into the bidding and contract documents and acknowledged by all bidders for the above referenced project. Bids submitted that do not acknowledge this Addendum will be deemed incomplete and may be rejected on such basis.

- 1. **Figures:** Please refer to Attachment 1 for Figures 1-4: Site Maps.
- 2. Supplemental Asbestos Survey: ATC Group Services has been retained by Genesee County Land Bank Authority to assist in bid specification preparation and to conduct project oversight. ATC has completed supplemental sampling of suspect asbestos containing materials. Supplements survey is attached as Attachment 2. Abatement of all identified ACM is to be incorporated into Bid Item 2 and Section 02 82 13.41 ASBESTOS ABATEMENT AND HAZARDOUS/REGULATED MATERIAL REMOVAL FOR TOTAL DEMOLITION PROJECTS.

Each bidder must acknowledge receipt of this addendum on RFP SUBMITTAL REQUIREMENTS CHECKLIST.

\*\*END OF ADDENDUM\*\*

Prepared by: Genesee County Land Bank 452 S. Saginaw St., Second Floor



# **ATTACHMENT 1**





APPROXIMATE PROPERTY BOUNDARY (SITE)

BUILDING NUMBER



ATC

46555 HUMBOLDT DRIVE, SUITE 100 NOVI, MI 48377 PH: 248-669-5140 FAX: 248-669-5147 FMAII: WWW ATCGROUPSERVICES (

> DATE: 3/19/18

PROJECT NO.: 188BS18146

DRAWN BY: LJH

NO SCALE

REVIEWED BY: MG

FIGURE 1

### SITE MAP



APPROXIMATE
PROPERTY
BOUNDARY (SITE)

**BUILDING NUMBER** 

JERSEY APPROXIMATE LOCATION OF BARRIER



ATC

555 HUMBOLDT DRIVE, SUITE 100 VI, MI 48377 : 248-669-5140 X: 248-669-5147

> DATE: 3/27/18

PROJECT NO.: 188BS18146

DRAWN BY: LJH

NO SCALE

REVIEWED BY: MG FIGURE 4

### **ALTERNATE #3**



APPROXIMATE
PROPERTY
BOUNDARY (SITE)

1

77777

**BUILDING NUMBER** 

APPROXIMATE LOCATION OF ROW DRIVEWAY





555 HUMBOLDT DRIVE, SUITE 100 DVI, MI 48377 I: 248-669-5140 X: 248-669-5147

> DATE: 3/27/18

PROJECT NO.: 188BS18146

DRAWN BY: LJH

NO SCALE

REVIEWED BY: MG FIGURE 3

### ALTERNATE #2



APPROXIMATE
- PROPERTY
BOUNDARY (SITE)

1

**BUILDING NUMBER** 



APPROXIMATE LOCATION OF APPROACHES



ATC

555 HUMBOLDT DRIVE, SUITE 100 DVI, MI 48377 1: 248-669-5140 X: 248-669-5147 MAIL: WWW ATCGROUPSERVICES CO

> DATE: 3/27/18

PROJECT NO.: 188BS18146

DRAWN BY: LJH

NO SCALE

REVIEWED BY:


FIGURE 2

### **ALTERNATE #1**

# **ATTACHMENT 2**



# Supplemental Pre-Demolition Asbestos Survey



Prepared for:

Genesee County Land Bank

March 29, 2018



# **Document Information**

Prepared for Genesee County Land Bank

Project Name 810 S. Ballenger Hwy

File Reference Genesee County.810 Ballenger

Job Reference 188BS18146 Date March 29, 2018

### **Contact Information**

### **ATC Group Services LLC**

46555 Humboldt, Suite 100

Novi, Michigan 48377 Telephone: 248.669.5140 Facsimile: 248.669.5147 www.atcgroupservices.com

### **Document Control**

		Initials		Initials
3/2018 K	im Johnson	KJ	Ryan Rae	RR
9/2018 K	im Johnson	KJ	Ryan Rae	RR
		3/2018 Kim Johnson	2/2018 Kim Johnson KJ	2/2018 Kim Johnson KJ Ryan Rae

Ryan Rae

Project Manager

for ATC

Direct Line +1 248-669-5140 Email: ryan.rae@atcgs.com Robert Smith

**Building Sciences Department Manager** 

Robert C. Kiniz

for ATC

Direct Line +1 248-669-5140 Email:robert.smith@atcgs.com

# **Executive Summary**

ATC Group Services LLC (ATC) has completed the supplemental pre-demolition asbestos survey for the multifamily residential property (apartment complex) located at 810 S. Ballenger Highway, Flint, Michigan. The information provided in the supplemental pre-demolition asbestos survey is intended to augment the original *Pre-Demolition Hazardous Material Survey*, dated November 23, 2016, prepared by AKT Peerless Environmental and Energy Services (AKT Peerless) and shall not be considered a "Stand Alone" document. Quantities of asbestos containing materials provided in ATC's supplemental pre-demolition survey are estimates only. The estimate quantities of ACM are provided for informational purposes only and are based on the best information available at the time of the specification preparation. The Abatement Contractor shall satisfy themselves as to the quantity of ACM materials and to the extent of the work.

One hundred ninety-seven (197) samples, taken from ninety-two (92) homogenous areas, were collected and submitted for analysis by PLM. The results of laboratory testing during the pre-demolition asbestos survey conducted at the property indicate that twenty-one (21) of the materials sampled were found to contain asbestos.

Based upon the drywall system composite sample results of drywall system samples collected by AKT Peerless, sample results were less than 1% asbestos, and therefore are not regulated by NESHAP, however it is regulated by MIOSHA as Class II work. Contractors that perform Work shall be a licensed abatement contractor and shall comply with all requirements of Class II work.

Non-friable, suspect ACM's such as roofing material, shall not be subjected to abrasion, grinding, sanding or any other processes during demolition activities which will render these non-friable materials friable.

Based on the NESHAP (National Emission Standards for Hazardous Air Pollutants) non-friable Category I ACM and Category I non-friable PACM roofing materials that are asphalt/tar based can be demolished with a building so long as it is in good condition and will not be cut, pounded, sanded, or grinded during demolition, and that measures are taken to ensure that it does not become friable, at which point will be considered RACM. However, Genesee County Land Bank Authority (GCLBA) policy requires Contractor to abate resilient floor coverings, prior to the demolition. Additionally, if demolition materials are going to be recycled, the Category I materials must be removed from the building prior to demolition activities. Additionally, it is the policy and practice of the GCLBA to abate what can feasibly be abated despite the condition of the structure, whether or not a structure will ultimately be demolished as asbestos containing (ordered/emergency demolition). Conditions inhibiting the abatement of ACM must be thoroughly documented, justified, and approved by the GCLBA and ATC prior to demolition. In addition, all roofing materials shall not be recycled if they contain ACM.

Lead containing paint sampling was not conducted as part of the scope of work and Contractors performing work at the site should assume materials within the building contain levels of lead above the detection limit. Contractors working onsite follow the OSHA Lead in Construction Standard to ensure the protection of their workers during demolition activities.

# **Table of Contents**

Exe	ecutive	Summary	iii
1		oduction	5
	1.1 1.2	Purpose Pre-Demolition Asbestos & Regulated Material Survey	5 5
2	Gen	eral Site Conditions	6
	2.1	General Property and Building Information	6
3	Pre-	Demolition Asbestos Survey	7
	3.1	Homogeneous Areas	7
	3.2	Hazard Assessment Factors	7
	3.3	Laboratory Analytical Methodology	7
	3.4	Sampling Results	8
4	Con	clusions and Recommendations	13
	4.1	Asbestos-Containing Materials	13
Ta	ables		
Tab	le 2-1	General Property and Building Information	6
Tab	ole 3-1	ACM Sampling Results	8

# **Appendices**

Appendix A ASBESTOS LABORATORY REPORTS

Appendix B QUALIFICATIONS

### 1 Introduction

### 1.1 Purpose

The purpose of this project was to conduct a supplemental pre-demolition asbestos survey at the multi-family residential property (apartment complex) located at 810 S. Ballenger Highway, Flint, Michigan, (herein referred to as "the property").

### 1.2 Pre-Demolition Asbestos & Regulated Material Survey

The scope of the supplemental pre-demolition asbestos survey included the following:

- > Review of existing asbestos reports for the building, if available;
- > Survey of the property building(s);
- > Identification of accessible suspect asbestos-containing materials (ACMs); and
- > Collection and analysis of bulk samples of suspect friable and non-friable materials.

# 2 General Site Conditions

### 2.1 General Property and Building Information

General property and building information is presented in the following table:

Table 2-1 General Property and Building Information

Date of Inspection:	March 23, 2018		
Inspector(s):	Joseph Seibert, Inspector Number A51777		
	Branden C. Tincu, Inspector Number A39513		
Property Address:	810 S. Ballenger Highway, Flint, Michigan, 48505		
Parcel Number(s):	NA		
Property Owner	Genesee County Land Bank		
Property Owner Address	452 S. Saginaw Street, Flint, Michigan, 48502		
Property Owner Telephone No.	810-257-3088 Ext. 539		
Building Construction Date:	NA		
Date(s) of Significant Renovations:	NA		
Building Description:	NA		
Building Square Footage (Approximate):	NA		

# 3 Pre-Demolition Asbestos Survey

ATC representatives, Mr. Joseph Seibert and Mr. Branden C. Tincu, conducted the supplemental pre-demolition asbestos inspection of the property buildings on March 23, 2018. Mr. Seibert and Mr. Tincu are State of Michigan Certified Asbestos Inspectors (Certification Nos. A51777 and A37593 respectively). Bulk samples of suspect ACMs were collected and placed into individual containers for transport to a National Voluntary Lab Accreditation Program (NVLAP)-accredited laboratory for analysis. Materials typically known as non-asbestos items (i.e. fibrous glass, foam rubber, wood, etc.) were not sampled. The asbestos inspection consisted of the following three basic procedures:

- > Conducting a visual inspection of the structures;
- > Identifying homogeneous areas (HAs) of suspect surfacing, thermal system insulation, and miscellaneous materials; and
- > Sampling accessible, friable and non-friable suspect materials.

### 3.1 Homogeneous Areas

Prior to collecting any samples, homogenous areas (HAs) were identified. A homogeneous sampling area can be described as one or more areas of material that are similar in appearance and texture and that have the same apparent installation date, appearance and function. Actual number of samples collected from each homogeneous sampling area may vary, based on the type of material and professional opinion of the inspector.

#### 3.2 Hazard Assessment Factors

From the list of suspect homogeneous areas, a physical assessment was performed for each material on the list. A physical assessment includes evaluating the condition, assessing the potential for disturbance, and determining the friability of each material. By definition, "friable" materials are those that can be crumbled or reduced to powder by hand pressure when dry. Each material identified was further classified into one of three categories: surfacing materials, thermal systems insulation (TSI) and miscellaneous materials. Each of the three categories have specific sampling requirements, outlined below.

- > Surfacing Materials: Refers to spray-applied or trowelled surfaces such as plaster ceilings and walls, fireproofing, textured paints, textured plasters, and spray-applied acoustical surfaces.
- > Thermal System Insulation: Refers to insulation used to inhibit heat gain or loss on pipes, boilers, tanks, ducts, and various other building components.
- > Miscellaneous Materials: Refers to friable and non-friable products and materials that do not fit in any of the above two categories such as resilient floor covering, baseboards, mastics, adhesives, roofing material, caulking, glazing, and siding. This category also contains wallboard and ceiling tile.

All materials were assessed related to their condition in one of the three categories: good (intact), fair (damaged) or poor (significantly damaged) per Title 40 Code of Federal Regulations Part 763. Material with localized, significant damage was also assessed as poor.

### 3.3 Laboratory Analytical Methodology

Bulk samples were analyzed by Apex Research, Inc., 11054 Hi Tech Drive, Whitmore Lake, Michigan 48189, using polarized-light microscopy (PLM) and dispersion staining (Method Reference: 40 CFR Part 763, Volume 47, No. 103, May 27, 1982 pg. 23376). This laboratory participates in the National Voluntary Laboratory Accreditation Program (NVLAP #102118-0), a quality assurance program for PLM analysis, and is accredited by the National Institute of Standards and Technology (NIST) as well as accreditation requirements under 15 CFR Part 25.

Copies of the laboratory analytical report and corresponding chain-of-custody forms are included in **Appendix A**. Positive sample results are reported in percent asbestos by volume of the sample and the type of asbestos material

within the sample. Other common non-asbestos components may also be noted on the analytical reports. Inspector and laboratory accreditations are provided in **Appendix B**.

### 3.4 Sampling Results

Bulk samples were collected from the site building and analyzed by polarized light microscopy (PLM), EPA Method 600/R-93/116. Twenty-one (21) of the materials sampled were found to contain concentrations of asbestos. The following table provides a summary of accessible suspect and confirmed ACMs from the Site buildings:

Table 3-1 ACM Sampling Results

Sample ID/Material	Material Description	Location of Materials	Condition	Friable Yes/No	Estimated Quantity	Asbestos Content
		Group 1 (Building 3 and	d 5)			
1-WG-A,B	Window glaze, Vertical/openable basement windows (15)	Exterior	Good	No	15 windows/34 0 LF	ND
2-WG-A,B	Window glaze, 2 pane small windows (45)	Exterior	Good	No	45 windows/ 360 LF	2% Chrysotile
3-VB-A,B	Vapor board,	Exterior walls	Good	No	40,000 SF	ND
4-EC-A,B	Exterior caulk, Dark gray	On all basement windows	Good	No	30 SF	2% Chrysotile
5-EC-A,B	Exterior caulk, light gray	Used at expansion joint and brick cracks	Good	No	200 LF	ND
6-EC-A,B	Exterior caulk, light gray with sparkles	On wood around all windows and doors	Good	No	130 SF	2% Chrysotile
7-EC-A,B	Exterior caulk, painted blue	On mailboxes (34 mailboxes)	Good	No	6 SF	5% Chrysotile
8-GM-A,B	Ceramic tile grout and mortar, 4" white	Debris around building	Good	No	100 SF	ND
9-BM-A,B	Brick mortar, exterior	Exterior brick	Good	No	20,000 SF	ND
10-BM-A,B	Block mortar, interior	Basements	Good	No	15,000 SF	ND
11-CC-A,B	Concrete chip, poured walls	Interior basement	Good	No	27,000 SF	ND
12-CC-A,B	Concrete chip, floor	Interior basement floor	Good	No	27,000 SF	ND
13-VP-A,B	Vapor paper	Under floors	Good	No	54,000 SF	ND
14-GM- A,B	Ceramic tile grout and mortar, 4" blue gray	Bathroom walls	Good	No	200 SF	ND
15-GM-A,B	Ceramic tile grout and mortar, 1"x1" blue gray	Bathroom floors	Good	No	160 SF	ND
16-CC-A,B	Concrete Chip,	Window sills	Good	No	150 SF	ND
17-WBS-A,B,C	Wall-board system, tape and mud	Throughout buildings in group 1	Good	No	24,000 SF	ND
18-BI-A,B,C	Blown in insulation, brown	Exterior walls	Good	No	700 CY	ND

SAMPLED MARCH 23, 2018						
Sample ID/Material	Material Description	Location of Materials	Condition	Friable Yes/No	Estimated Quantity	Asbestos Content
19-WG-A,B	Window glaze,	Interior fire door with reinforced glass	Good	No	160 LF	10% Chrysotile
20-WG-A,B	Window glaze,	Stairwell windows, tilt in	Good	No	72 LF	ND
21-EC-A,B	Exterior caulk,	Along roof board	Good	No	1000 LF	ND
22-CA-A,B	Construction adhesive,	Bathroom sinks	Good	No	160 LF	ND
23-SC-A,B,C	Stack cement	FS 445, 417, 448	Good	No	20 SF	10% Chrysotile
24-CA-A,B	Construction adhesive	Kitchen counters	Good	No	200 LF	ND
25-FT-A,B	Floor tile, 9"x9" green	FS 445 west end	Good	No	80 SF	10% Chrysotile
26-FS-A,B	Floor sheeting, red	FS 445 storage closet 43	Good	No	40 SF	ND
27-BM-A,B	Brick mortar, black mastic	Basements (black mastic)	Good	No	500 LF	ND
28-FD-A,B	Fire door	Throughout	Good	No	15 doors	45% Chrysotile
		Group 2 (Building 4)				
1-BM-A,B	Brick mortar	Exterior brick	Good	No	500 CY	ND
2-CC-A,B	Concrete chip	Poured walls	Good	No	500 CY	ND
3-CC-A,B	Concrete chip	Front porch and rear porch	Good	No	260 SF	ND
4-CC-A,B	Concrete chip	Basement floors	Good	No	5,000 SF	No sample received
5-IC-A,B	Interior Caulk	On cabinets	Good	No	300 LF	ND
6-CC-A,B	Concrete chip	Window sills	Good	No	50 SF	ND
7-TU-A,B	Tub undercoating, black	Bathtubs	Good	No	80 SF	5% Chrysotile
8-VB-A,B	Vapor board	Under exterior brick	Good	No	8,800 SF	ND
9-VP-A,B	Vapor paper	Under wood floors	Good	No	8,000 SF	ND
10-WG-A,B	Window glaze	2 pane basement windows (30)	Good	No	30 windows/ 250 LF	0.25% Chrysotile (PC)
11-SC- A,B,C,D,E	Stack Cement	Chimney stacks Units 29-38	Good	No	60 SF	2% Chrysotile
12-EC-A,B	Exterior caulk	On brick, roofline, doors, windows, basement windows mailboxes	Good	No	160 SF	2% Chrysotile
13-EC-A,B	Exterior caulk	On aluminium overhangs at doors	Good	No	40 LF	ND

SAMPLED MARCH 23, 2018						
Sample ID/Material	Material Description	Location of Materials	Condition	Friable Yes/No	Estimated Quantity	Asbestos Content
14-BM- A,B	Brick mortar	Patching around air conditioning units	Good	No	30 SF	ND
15-GM-A,B	Ceramic tile grout and mortar, 4" light blue/gray	Throughout building on bathroom walls	Good	No	800 SF	ND
16-GM-A,B	Ceramic tile grout and mortar, 1"x2" light blue/gray	Throughout building on bathroom floors	Good	No	400 SF	ND
17-CA-A,B	Construction adhesive, panel board tan	Throughout building on kitchen backsplash	Good	No	160 LF	ND
18-CA-A,B	Construction adhesive, panel board white	Throughout building	Good	No	200 LF	ND
19-WBS-A,B,C	Wall-board system, tape and mud	Throughout building	Good	No	9,000 SF	0.25% Chrysotile  — Joint Compound (PC) ND – Wallboard/ Drywall
20-IC-A,B	Interior caulk	In bathrooms on 4" tile	Good	No	300 LF	ND
21-BM-A,B	Black mastic	On basement joists	Good	No	500 LF	ND
22-FT-A,B	Floor tile, 9"x9" beige with tan speckle	FS 377 unit 38	Good	No	20 SF	5% Chrysotile
23-FS-A,B	Floor sheeting, 5" square linoleum	Bar top FS377 unit 38	Good	No	14 SF	ND
24-FT-A,B	Floor tile, 9" tan and beige	Basement unit 29	Good	No	30 SF	5% Chrysotile
25-CT-A,B	Ceiling tile, 12' Smooth	Basement unit 29 and unit 36	Good	No	80 SF	ND
26-FS-A,B	Floor sheeting, 8" square brown stone	Unit 32	Good	No	60 SF	ND
27-CA-A,B	Construction adhesive black in kitchen	Unit 30	Good	No	100 LF	5% Chrysotile
28-MLF-A,B	Multi-layer flooring	Kitchen unit 30	Good	No	80 SF	30% Chrysotile
29-FT-A,B	Floor tile, 12" beige with brown mottle	Unit 34,31,29,37,38	Good	No	500 SF	ND
30-FT-A,B	Floor tile, 12" beige with black mottle	Unit 33,35	Good	No	200 SF	ND
31-MLF-A,B	Multi-layer flooring	Unit 36	Good	No	80 SF	ND
	Group 3 (Building 1 and 2)					
1-VB-A,B	Vapor Board	Behind exterior brick	Good	No	18,000 SF	ND
2-VP-A,B	Vapor paper	Under wood floors	Good	No	16, 000 SF	ND
3-WG-A,B	Window glaze	Aluminium frame windows	Good	No	150 LF	ND
4-WG-A,B	Window glaze	Basement metal old windows	Good	No	600 LF	ND
5-WG-A,B	Window glaze	Basement metal new windows	Good	No	400 LF	ND

SAMPLED MARCH 23, 2018						
Sample ID/Material	Material Description	Location of Materials	Condition	Friable Yes/No	Estimated Quantity	Asbestos Content
6-EC-A,B	Exterior Caulk	Doors, windows, basement windows, mailboxes	Good	No	242 SF	5% Chrysotile
7-EC-A,B	Exterior Caulk	Air conditioning units	Good	No	140 LF	ND
8-WBS-A,B,C	Wall-board system	Throughout the buildings	Good	No	24,500 SF	0.5% Chrysotile – Joint Compound (PC) ND – Wallboard/ Drywall *
9-SC-A,B,C,D,E	Stack cement	Chimney stacks in the buildings	Good	No	60 SF	ND
10-EC-A,B	Exterior Caulk	On porch metal poles	Good	No	30 LF	ND
11-BM-A,B	Brick mortar	Exterior	Good	No	30,000 SF	ND
12-CC-A,B	Concrete chip	Porches	Good	No	80 CY	ND
13-CC-A,B	Concrete chip	Window sills	Good	No	50 SF	ND
14-FI- A,B	Felt insulation	Air conditioning units	Good	No	400 SF	ND
15-IC-A,B	Interior caulk	Window frames	Good	No	300 LF	ND
16-IC-A,B	Interior caulk	Kitchen cabinets	Good	No	100 LF	ND
17-WB-A,B	Wall-board	Green board in basement of unit 1	Good	No	20 SF	ND
18-DG-A,B	Door gasket	FS 11	Good	No	20 LF	ND
19-CC-A,B	Concrete chip	Poured walls	Good	No	400 CY	ND
20-CC-A,B	Concrete chip	Basement floors	Good	No	12,000 SF	ND
21-WG-A,B	Window glaze	Egress windows	Good	No	60 LF	Trace Chrysotile (PC)
22-CT-A,B	Ceiling tile, 12" smooth	FS 173	Good	No	80 SF	ND
23-TU-A,B	Tub undercoating	Bathrooms	Good	No	150 SF	5% Chrysotile
24-DW-A,B,C	Duct wrap	Basement of unit 4	Good	No	1 SF	60% Chrysotile
25-GM-A,B	Ceramic tile grout and mortar, 1"x1" gray	Bathroom walls	Good	No	1,100 SF	ND
26-GM-A,B	Ceramic tile grout and mortar, 4"x4" gray	Bathroom floors	Good	No	820 SF	ND
27-FS-A,B	Floor sheeting, Beige with tan crackle	FS 141	Good	No	60 SF	ND
28-WG-A,B	Window glaze	Aluminium window, unit 16 and 28	Good	No	120 LF	5% Chrysotile

Sample ID/Material	Material Description	Location of Materials	Condition	Friable Yes/No	Estimated Quantity	Asbestos Content
29-GM-A,B	Ceramic tile grout and mortar, 12"x12" Beige	FS 163, 164	Good	No	120 SF	ND
30-FT-A,B	Floor tile, 9"x9" beige wood grain	FS 196	Good	No	60 SF	5% Chrysotile – FT 5% Chrysotile - Mastic
31-CP-A,B	Ceiling panel, 18"x3' smooth	FS 196	Good	No	80 SF	ND
32-BM-A,B	Black mastic	All basements (rope insulation)	Good	No	508 LF	5% Chrysotile
31-VP-A,B	Vapor Paper	Exterior wall, FS 117	Good	No	100 SF	ND

ND: None Detected s.f./l.f/c.y.: square feet/linear feet/cubic yard VFT: Vinyl Floor Tile

A: Not Applicable M: Miscellaneous S: Surfacing

FSI: Thermal System Insulation PACM: Presumed ACM NQ: Not Quantified

**NESHAP** 

RACM: Regulated ACM Cat. II: Category I Non-Friable ACM Cat. II: Category II Non-Friable ACM

\*Based upon the drywall system composite sample results of drywall system samples collected by AKT Peerless, sample results were less than 1% asbestos, and therefore are not regulated by NESHAP, however it is regulated by MIOSHA as Class II work. Contractors that perform Work shall be a licensed abatement contractor and shall comply with all requirements of Class II work.

In the event additional suspect material is discovered during demolition activities, this material should be treated as presumed asbestos-containing material (PACM) in accordance with regulations 29 CFR 1926.1101 and 1910.1001 and other applicable state and local regulations and either sampled to confirm or nullify asbestos content or be treated as ACM and abated at no additional cost to the GCLBA.

# 4 Conclusions and Recommendations

### 4.1 Asbestos-Containing Materials

The results of laboratory testing during the pre-demolition asbestos survey conducted at the property indicate that twenty-one (21) of the materials sampled were found to contain asbestos. If these materials cannot be removed safely prior to demolition, the Contractor performing the work should comply with all requirements of OSHA and all building materials should be treated as ACM waste and disposed according to the requirements of NESHAP. If materials identified to contain asbestos can be removed safely they should be removed prior to demolition by a licensed abatement company.

Based upon the drywall system composite sample results of drywall system samples collected by AKT Peerless, sample results were less than 1% asbestos, and therefore are not regulated by NESHAP, however it is regulated by MIOSHA as Class II work. Contractors that perform Work shall be a licensed abatement contractor and shall comply with all requirements of Class II work.

Access to some areas within the structure were limited due to unsafe conditions and materials not identified in this report may be present within the building. The approximate quantity of asbestos materials and materials contaminated with asbestos were estimated and Contractors that intend to bid on removal of this material should not rely on the exact quantities estimated in this report. Contractors should conduct an assessment of the property to determine the time and effort required to complete the scope of work for the proper removal and disposal of asbestos and asbestos contaminated materials.

Non-friable ACM's shall not be subjected to abrasion, grinding, sanding or any other processes during renovation activities which will render these non-friable materials friable.

Based on the NESHAP (National Emission Standards for Hazardous Air Pollutants) non-friable Category I ACM and Category I non-friable PACM roofing materials that are asphalt/tar based can be demolished with a building so long as it is in good condition and will not be cut, pounded, sanded, or grinded during demolition, and that measures are taken to ensure that it does not become friable, at which point will be considered RACM. However, Genesee County Land Bank Authority 's (GCLBA) policy requires Contractor to abate resilient floor coverings, prior to the demolition. Additionally, if demolition materials are going to be recycled, the Category I materials must be removed from the building prior to demolition activities. Additionally, it is the policy and practice of the GCLBA to abate what can feasibly be abated despite the condition of the structure, whether or not a structure will ultimately be demolished as asbestos containing (ordered/emergency demolition). Conditions inhibiting the abatement of ACM must be thoroughly documented, justified, and approved by the GCLBA and ATC prior to demolition. In addition, all roofing materials shall not be recycled if they contain ACM.

This statement is in lieu of other statements either expressed or implied. This report does not warrant against changes to material from future operations or conditions, nor does it warrant against operations or conditions against present ACM materials.

The scope of services performed in execution of this evaluation may not be appropriate to satisfy the needs of other users, and use or re-use of this document or the findings, conclusions, or recommendations is at the risk of said user.

810 S. Ballenger Hwy

# APPENDIX A ASBESTOS LABORATORY REPORTS



### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: 75873 - 01

1-BM-A

Cust. #: Material:

**Brick Mortar** 

Location: Exterior Brick

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75873 - 02

Cust. #:

1-BM-B

Material:

**Brick Mortar** 

Location: Exterior Brick

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75873 - 03

Cust. #: Material: 2-CC-A

Concrete Chip/Plaster

Location: Poured Walls

Appearance: white, nonfibrous, nonhomogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Robert T. Letarte Jr., Laboratory Director

### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 03a

Cust. #:

2-CC-A

Material:

Mortar

Location: Poured Walls

Appearance: grey,nonfibrous,homogenous

Layer:

Lab ID #:

75873 - 04

Cust. #:

2-CC-B

Material:

Concrete Chip/Mortar

Location: Poured Walls

Appearance: grey,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75873 - 05

Cust. #:

3-CC-A

Material:

Concrete Chip

Location: Front Porch and Rear Porch

Layer:

Appearance: grey,nonfibrous,homogenous

of

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Other - 100%

Other - 100%

Other - 100%

Asbestos Present: NO No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 06

Cust. #:

3-CC-B

Material:

Concrete Chip

Location: Front Porch and Rear Porch Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75873 - 07

Cust. #:

4-CC-A

Material:

Concrete Chip

Location: Basement Floors

Appearance:

Layer:

of

Lab ID #:

75873 - 08

Cust. #:

Concrete Chip

Location:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present:

Asbestos Present:

NO SAMPLE RECEIVED

4-CC-B

Material:

**Basement Floors** 

NO SAMPLE RECEIVED

Appearance: Layer:

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 09

Cust. #: 5-IC-A

Material: Interior Caulk Location: On Cabinets

Appearance: grey,nonfibrous,nonhomogenous

Layer: of

Lab ID #:

75873 - 10

Cust. #:

5-IC-B

Material:

Interior Caulk

Location: On Cabinets

Appearance: white, nonfibrous, homogenous

Layer:

of

Cust. #:

Lab ID #: 75873 - 11

Material:

6-CC-A

Concrete Chip

Location: Window Sills

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 12 6-CC-B

Cust. #:

Material:

Concrete Chip Location: Window Sills

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 13

Cust. #:

7-TU-A

Material:

Tub Undercoating, Black

Location: Bathtubs

Appearance: black, fibrous, homogenous

Layer: of

Lab ID #: 75873 - 14

Cust. #: Material: 7-TU-B

Tub Undercoating, Black

Location:

Appearance:

Bathtubs

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Cellulose - 2%

Other - 98%

Other - 95%

Asbestos Present: YES

Chrysotile - 5%

Asbestos Present:

NOT ANALYZED

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 15 8-VB-A

Cust. #:

Material:

Vapor Board Location: Under Exterior Brick

Appearance: black, fibrous, homogenous Layer:

Lab ID #:

75873 - 16

Cust. #:

8-VB-B

Material:

Vapor Board

Location: Under Exterior Brick

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #: 75873 - 17

Cust. #:

9-VP-A

Material:

Vapor Paper

Location: Under Wood Floors

of

Asbestos Present: NO

No Asbestos Observed

Cellulose - 60%

Other - 40%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 60% Other - 40%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 40% Other - 60%

Appearance: black, fibrous, homogenous

Layer:

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Cellulose - 40%

Other - 60%

Other - 100%

Other - >99%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

Chrysotile - <1%

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 18

Cust. #: Material: 9-VP-B

Vapor Paper

Location: Under Wood Floors Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75873 - 19

Cust. #:

10-WG-A

Material:

Window Glaze

Location: 2 Pane Basement Windows (30) Appearance: grey,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75873 - 20

Cust. #:

10-WG-B

Material:

Window Glaze

Location: 2 Pane Basement Windows (30)

Appearance: grey,fibrous,nonhomogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

1

of

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received:

Other - 99.75%

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: **NO** 

POINT COUNT RESULT

Chrysotile - 0.25%

Non-Asbestos Material

Lab ID #:

75873 - 20-pc

Cust. #:

10-WG-B

Material:

Window Glaze

Location: 2 Pane Basement Windows (30)

Appearance: grey,fibrous,nonhomogenous

Layer:

of

Asbestos Present: YES

Other - 98%

Lab ID #: Cust. #:

75873 - 21 11-SC-A

Material:

Stack Cement

Location: Chimney Stacks

Appearance: grey,fibrous,homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Lab ID #:

75873 - 22

Cust. #:

11-SC-B

Material:

Stack Cement

Location:

Chimney Stacks

Appearance:

Asbestos Present:

Chrysotile - 2%

NOT ANALYZED

Layer:

of

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:	ARI Report #	18-75873
Mr. Rob Smith	Date Collected:	03/23/18
ATC Group Services, LLC	Date Received:	03/27/18
46555 Humboldt, Ste. 100	Date Analyzed:	03/28/18
Novi. MI 48377	Date Reported:	03/28/18

Novi, MI 483//		Date Reported: 03/28/18
Sample Information	Asbestos Type/Percent	Non-Asbestos Material
Lab ID #: 75873 - 23	Asbestos Present:	
Cust. #: 11-SC-C		
Material: Stack Cement		
Location: Chimney Stacks	NOT ANALYZED	
Appearance:		
Layer: of		
Lab ID #: 75873 - 24	Asbestos Present:	
Cust. #: 11-SC-D		
Material: Stack Cement		
Location: Chimney Stacks	NOT ANALYZED	
Appearance:		
Layer: of		
Lab ID #: 75873 - 25	Asbestos Present:	
Cust. #: 11-SC-E		
Material: Stack Cement	NOT ANALYZED	
Location: Chimney Stacks	NOT ANALYZED	
Appearance:		
Layer: of		

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director



## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 26

Cust. #:

12-EC-A

Ext. Caulk, On Brick, Roofline, Doors Material: Location: Windows, Bsmt Windows Mailboxes

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 27

12-EC-B

Material:

Ext. Caulk, On Brick, Roofline, Doors

Location:

Windows, Bsmt Windows Mailboxes

Appearance:

Layer:

of

Lab ID #:

75873 - 28

Cust. #:

13-EC-A

Material:

Exterior Caulk

Location: On Aluminum Overhangs at Doors

Appearance: beige, nonfibrous, homogenous

Layer:

of

Asbestos Present: YES

Chrysotile - 2%

Other - 98%

Cust. #:

NOT ANALYZED

Asbestos Present:

Asbestos Present: NO

No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

Other - 100%

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 29

Cust. #:

13-EC-B

Material:

Exterior Caulk

Location: On Aluminum Overhangs at Doors

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75873 - 30

Cust. #:

14-BM-A

Material:

**Brick Mortar** 

Location: Patching Around Air Conditioning Units

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75873 - 31

Cust. #:

14-BM-B

Material:

**Brick Mortar** 

Location: Patching Around Air Conditioning Units

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 32

Cust. #:

15-GM-A

Material:

Ceramic Tile 4" Lt Blue/Grey Grout

Location:

**Throughout Building** 

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75873 - 32a

Cust. #:

15-GM-A

Material:

Mortar

Location: Throughout Building

Appearance: grey,nonfibrous,homogenous

Layer: 2

of

Lab ID #: 75873 - 33

Cust. #:

15-GM-B

Material:

Ceramic Tile 4" Lt Blue/Grey Grout

Location: Throughout Building

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 33a

Cust. #:

15-GM-B

Material:

Mortar

Location: Throughout Building

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75873 - 34

Cust. #:

16-GM-A

Material: Ceramic 1"x2" Lt Blue/Grey, Grout/Mortar

Location: Throughout Building

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75873 - 35

Cust. #: 16-GM-B

Material:

Location: Throughout Building

Appearance: grey,nonfibrous,homogenous

Ceramic 1"x2" Lt Blue/Grey, Grout/Mortar

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed:

Cellulose - 20%

Other - 80%

Other - 100%

Other - 100%

03/27/18

Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 36

Cust. #: Material:

17-CA-A

Construction Adhesive, Panel Board Tan Throughout Building

Location:

Appearance: yellow,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 37

Cust. #:

17-CA-B

Material:

Construction Adhesive, Panel Board Tan

Location: Throughout Building

Appearance: yellow,nonfibrous,homogenous Layer:

of

Lab ID #: 75873 - 38

Cust. #:

18-CA-A

Material:

Construction Adhesive

Location: Panel Board White - Throughout Building

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

## Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 39

Cust. #:

18-CA-B

Material:

Construction Adhesive

Location: Panel Board White - Throughout Building

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75873 - 40

Cust. #:

19-WBS-A

Material:

Wallboard/Drywall

Location: Throughout Building Appearance: white, fibrous, homogenous

Layer:

of

Lab ID #: 75873 - 40a

Cust. #:

19-WBS-A

Material:

Joint Compound

Location: Throughout Building Appearance: white, fibrous, homogenous

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 20%

Other - >99%

Other - 80%

Asbestos Present: **NO** 

Chrysotile - <1%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Non-Asbestos Material

Lab ID #:

75873 - 40a-pc

Cust. #:

19-WBS-A

Material:

Joint Compound

Location:

Throughout Building

Appearance: white, fibrous, homogenous

Layer:

of

75873 - 41

Lab ID #: Cust. #:

19-WBS-B

Material:

Joint Compound Location: Throughout Building

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #: 75873 - 41-pc

Cust. #:

19-WBS-B

Material:

Joint Compound

Location:

Throughout Building

Appearance: beige, fibrous, homogenous

Layer:

of

Asbestos Type/Percent

Other - 100%

Asbestos Present: **NO** 

Chrysotile - Trace

POINT COUNT RESULT

Asbestos Present: NO

Chrysotile - <1%

Other - >99%

Other - 99.75%

Asbestos Present: **NO** 

Chrysotile - 0.25%

POINT COUNT RESULT

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Cellulose - 20%

Cellulose - 20%

Other - 80%

Other - >99%

Other - 80%

03/28/18

Date Reported:

03/28/18

#### Sample Information

#### Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

Chrysotile - <1%

No Asbestos Observed

No Asbestos Observed

#### Non-Asbestos Material

Lab ID #: Cust. #:

75873 - 41a 19-WBS-B

Material:

Location:

Wallboard/Drywall Throughout Building

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 42

Cust. #:

19-WBS-C

Material:

Wallboard/Drywall

Location: Throughout Building

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75873 - 42a

Cust. #:

19-WBS-C

Material:

Joint Compound

Location: Throughout Building

Appearance: beige, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: **NO** 

POINT COUNT RESULT

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Chrysotile - Trace

Non-Asbestos Material

Lab ID #:

75873 - 42a-pc

Cust. #:

19-WBS-C

Material:

Joint Compound

Location:

Throughout Building

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75873 - 43

Cust. #:

20-IC-A

Material:

Interior Caulk

Location: In Bathrooms on 4" Tile

Layer:

Appearance: white, nonfibrous, homogenous of

Lab ID #: 75873 - 44

Cust. #:

20-IC-B

Material:

Interior Caulk

Location: In Bathrooms on 4" Tile

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 95%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **YES** 

Chrysotile - 5%

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 45

Cust. #:

21-BM-A

Material:

Black Mastic On Basement Joists

Location:

Appearance: black,nonfibrous,homogenous

Layer:

of

Lab ID #:

75873 - 46

Cust. #:

21-BM-B

Material:

**Black Mastic** 

Location: On Basement Joists

Appearance: black,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75873 - 47

Cust. #:

22-FT-A

Material: Floor Tile 9"x9" Beige w/ Tan Specks

Location: FS 377 Unit 38

Appearance: brown, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Fiberglass - 20%

Cellulose - 10%

Fiberglass - 10%

Other - 80%

Other - 80%

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 48

Cust. #:

22-FT-B

Material:

Floor Tile 9"x9" Beige w/ Tan Specks

Location: FS 377 Unit 38

of

NOT ANALYZED

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Asbestos Present:

Appearance:

Layer:

Lab ID #:

75873 - 49

Cust. #:

23-FS-A

Material:

Floor Sheeting 5" Square Linoleum

Location: Bar Top FS377 Unit 38

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75873 - 50

Cust. #:

23-FS-B

Material:

Floor Sheeting 5" Square Linoleum

Location: Bar Top FS377 Unit 38

Appearance: grey,fibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 95%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: YES

Asbestos Present: NO

No Asbestos Observed

Chrysotile - 5%

Non-Asbestos Material

Lab ID #:

75873 - 51

Cust. #:

24-FT-A

Material:

Floor Tile 9" Tan/Beige

Location: Basement Unit 29

Appearance: brown,fibrous,homogenous

Layer:

Lab ID #:

75873 - 51a

Cust. #:

24-FT-A Mastic

Material:

Location: Basement Unit 29

Appearance: black,nonfibrous,homogenous

Layer: 2

of

Lab ID #: 75873 - 52

Cust. #: Material: 24-FT-B

Floor Tile 9" Tan/Beige

Location:

Basement Unit 29

NOT ANALYZED

Asbestos Present:

Appearance:

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed:

Cellulose - 90%

Cellulose - 90%

Fiberglass - 10%

Other - 90%

Other - 10%

Other - 10%

03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 53

Cust. #:

25-CT-A

Material:

Ceiling Tile, 12' Smooth Location: Basement Unit 29 and Unit 36

Appearance: brown, fibrous, homogenous

Layer:

of

Lab ID #:

75873 - 54

Cust. #:

25-CT-B

Material:

Ceiling Tile, 12' Smooth

Location: Basement Unit 29 and Unit 36

Appearance: brown,fibrous,homogenous Layer:

of

Lab ID #: 75873 - 55

Cust. #:

26-FS-A

Material:

Floor Sheeting, 8" Square Brown Stone

Location: Unit 32

Appearance: brown, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Fiberglass - 10%

Other - 90%

Other - 95%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: YES

Chrysotile - 5%

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75873 - 56

26-FS-B

Floor Sheeting, 8" Square Brown Stone

Material:

Location: Unit 32

Appearance: brown,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 57

Cust. #:

27-CA-A

Material:

Construction Adhesive, Black

Location: In Kitchen, Unit 30

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75873 - 58

Cust. #:

27-CA-B

Material:

Construction Adhesive, Black

Location: In Kitchen, Unit 30

**NOT ANALYZED** 

Asbestos Present:

Appearance: Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received:

Other - 70%

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 59

Cust. #:

28-MLF-A

Material:

Multilayer Flooring/Linoleum

Location:

Kitchen Unit 30

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75873 - 59a

Cust. #:

28-MLF-A

Material:

Multilayer Flooring

Location: Kitchen Unit 30

Appearance: brown,fibrous,homogenous

Layer:

of

Lab ID #:

75873 - 60

Cust. #:

Material:

Multilayer Flooring/Linoleum

Location:

Kitchen Unit 30

of

Asbestos Present: YES

Chrysotile - 30%

Asbestos Present: YES

Chrysotile - 30%

Other - 70%

Asbestos Present:

28-MLF-B

For Layered Samples, each component will be analyzed and reported separately.

NOT ANALYZED

Appearance: Layer:

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 61

Cust. #:

29-FT-A

Material:

Floor Tile, 12" Beige w/ Brown Mottle

Location: Unit 34, 31, 29, 37, 38

Appearance: white, nonfibrous, homogenous Layer:

of

75873 - 62

Cust. #:

29-FT-B

Material:

Lab ID #:

Floor Tile, 12" Beige w/ Brown Mottle

Location: Unit 34, 31, 29, 37, 38

Appearance: white, nonfibrous, homogenous

Layer: 1 of

Lab ID #: 75873 - 63

Cust. #:

30-FT-A

Material:

Floor Tile, 12" Beige w/ Black Mottle

Location: Unit 33, 35

Appearance: grey,nonfibrous,homogenous

Layer: 1 of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75873 - 64

Cust. #: 30-FT-B

Material:

Floor Tile, 12" Beige w/ Black Mottle

Location: Unit 33, 35

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75873 - 65

Cust. #:

31-MLF-A

Material:

Multilayer Flooring

Location: Unit 36

Appearance: white, nonfibrous, homogenous

1 of

Layer:

Lab ID #: 75873 - 65a

Cust. #:

31-MLF-A

Material:

Multilayer Flooring

Location: Unit 36

Appearance: grey,nonfibrous,homogenous

Layer:

2 of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 2 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75873

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75873 - 66

Cust. #:

31-MLF-B

Material:

Multilayer Flooring

Location:

Unit 36

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75873 - 66a

Cust. #:

31-MLF-B

Material:

Multilayer Flooring

Location: Unit 36

Appearance: grey,nonfibrous,homogenous

Layer: 2 of

Lab ID #:

Cust. #: Material:

Location:

Appearance: Layer:

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Other - 100%


Asbestos Present:

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Apex Research, Inc.

11054 Hi Tech Drive, Whitmore Lake, MI 48189. Phone: (734) 449-9990, Fax: (734) 449-9991.



Relinquished By: Joseph Seibert

Web Site: http://apexresearch-inc.com

3Client Name:

**ATC Group Services** 

Date of Survey: \_\_\_

3-23-2018

Address:

46555 Humboldt Drive, Suite 100

**Project:** 810 S. Ballenger Highway-Group 2

City, St., Zip:

Novi, MI 48377

**Project #:** 188BS18146

Phone:

(248) 669-5140

Fax:

(248)-669-5147

Contact Person: Rob Smith

Date: \_\_\_\_\_3/26/1

Received By:

MAR 2 7 2018

Date:

Special Instructions RESEARCH

1st Positive Stop;


- Composite all drywall/joint compound samples if any layer of system is greater than 5% asbestos;
- Point Count ALL PLASTER samples Trace to 3% asbestos content
- Point Count ALL SAMPLES Trace to 1%

Around Time: (CircleOne)	Rush	24 Hour X	48 Hour	72 Hour	Other:	TTP (Test Till Positive)
Asbestos	Bul	k X	Point Count_		PCM	
Lah ID		******				

Lab ID #	Client ID#	Material	Location	Quantity	Area	Results
1,2	1-BM-A,B	Brick mortar	Exterior brick			
3,4	2-CC-A,B	Concrete chip	Poured walls			
5,6	3-CC-A,B	Concrete chip	Front porch and rear porch	260 SF		
7.5	4-CC-A,B	Concrete chip	Basement floors	5,000 SF		·
9,10	5-IC-A,B	Interior Caulk	On cabinets			
11,12	6-CC-A,B	Concrete chip	Window sills			
13.14	7-TU-A,B	Tub undercoating, black	Bathtubs	80 SF		
15,16	8-VB-A,B	Vapor board	Under exterior brick			
17,18	9-VP-A,B	Vapor paper	Under wood floors	8,000 SF		
19,26	10-WG-A,B	Window glaze	2 pane basement windows (30)	250 LF		
21-25		Stack Cement	Chimney stacks	60 SF		
26,2	7 12-EC-A,B	Exterior caulk	On brick, roofline, doors, windows, basement windows mailboxes			
24,7	(A) 13-EC-A,B	Exterior caulk	On aluminum overhangs at doors	40 LF		
47.3	<b>/</b> ₹ 14-BM- A,B	Brick mortar	Patching around air conditioning units	30 SF		

# 75873

#### Apex Research, Inc.





Web Site: http://apexresearch-inc.com

,	71 V	Bitte internaponicocarcii inc.	50111	
32,33 15-GM-A,B	Ceramic tile grout and mortar, 4" light blue/gray	Throughout building		
16-GM-A,B	Ceramic tile grout and mortar, 1"x2" light blue/gray	Throughout building		
26,37 17-CA-A,B	Construction adhesive, panel board tan	Throughout building		
34 34 18-CA-A,B	Construction adhesive, panel board white	Throughout building		
40-42 19-WBS-A,B,C	Wall-board system, tape and mud	Throughout building		
42.44 20-IC-A,B	Interior caulk	In bathrooms on 4" tile		
45 45 21-BM-A,B	Black mastic	On basement joists		
47,49 22-FT-A,B	Floor tile, 9"x9" beige with tan speckle	FS 377 unit 38	20 SF	
40,50 23-FS-A,B	Floor sheeting, 5" square linoleum	Bar top FS377 unit 38	14 SF	
<1,52 24-FT-A,B	Floor tile, 9" tan and beige	Basement unit 29	30 SF	
53,54 25-CT-A,B	Ceiling tile, 12' Smooth	Basement unit 29 and unit 36	80 SF	
55,56 26-FS-A,B	Floor sheeting, 8" square brown stone	Unit 32	60 SF	
57,56 27-CA-A,B	Construction adhesive black in kitchen	Unit 30	100 LF	
SA, 60 28-MLF-A,B	Multi-layer flooring	Kitchen unit 30	80 SF	
6),62 29-FT-A,B	Floor tile, 12" beige with brown mottle	Unit 34,31,29,37,38		
63,616 30-FT-A,B	Floor tile, 12" beige with black mottle	Unit 33,35		
65,66 31-MLF-A,B	Multi-layer flooring	Unit 36	80 SF	

The bull

Relinquished By: Joseph Seibert

Date: 3/26/18

Received By

MAR 2 7 2018

\*\*\*Terms and conditions on reverse side.

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 98%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **YES** 

Chrysotile - 2%

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 01

1-WG-A

Cust. #:

Exterior Window Glaze

Material:

Location: Vertical/Openable Basement Windows-15

Appearance: beige, nonfibrous, homogenous

Layer:

of

Lab ID #:

75875 - 02

Cust. #:

1-WG-B

Material:

Exterior Window Glaze

Location: Vertical/Openable Basement Windows-15

Appearance: beige,nonfibrous,homogenous

Layer:

of

Lab ID #: 75875 - 03

Cust. #:

2-WG-A

Material:

Window Glaze

Location: 2 Panel Small Windows (45) Exterior

Appearance: beige, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

Cellulose - 75%

Cellulose - 75%

Other - 25%

Other - 25%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 04

Cust. #:

2-WG-B

Material:

Window Glaze

Location: 2 Panel Small Windows (45) Exterior NOT ANALYZED

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Asbestos Present:

Appearance:

Layer:

of

Lab ID #:

75875 - 05

Cust. #:

3-VB-A

Material:

Vapor Board

Location: Exterior Walls

Appearance: brown,fibrous,nonhomogenous

Layer:

of

Lab ID #: 75875 - 06

Cust. #:

3-VB-B

Material:

Vapor Board

Location: Exterior Walls

Appearance: brown,fibrous,nonhomogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

Other - 98%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: YES

Chrysotile - 2%

Asbestos Present:

NOT ANALYZED

Asbestos Present: NO

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 07

4-EC-A

Cust. #: Material: Exterior Caulk, Dark Grey

Location: On All Basement Windows Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75875 - 08

Cust. #:

4-EC-B

Material:

Exterior Caulk, Dark Grey

Location: On All Basement Windows

Appearance:

Layer:

of

Lab ID #: 75875 - 09

Cust. #:

5-EC-A

Material: Exterior Caulk, Light Grey

Location: Used at Expansion Joint/Brick Cracks Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

Other - 100%

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 98%

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 10

Cust. #:

5-EC-B

Material:

Exterior Caulk, Light Grey

Location: Used at Expansion Joint/Brick Cracks Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 11

Cust. #:

6-EC-A

Material:

Exterior Caulk, Light Grey w/ Sparkles Location: On Wood Around All Windows/Doors

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75875 - 12

Cust. #: 6-EC-B

Material:

Exterior Caulk, Light Grey w/ Sparkles

Location:

On Wood Around All Windows/Doors

Appearance:

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Asbestos Present: **YES** 

Chrysotile - 2%

Asbestos Present:

NOT ANALYZED

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 13

Cust. #: 7-EC-A

Material: Exterior Caulk, Paint Blue

Location: On Mailboxes

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75875 - 14

Cust. #:

7-EC-B

Material:

Location:

Appearance:

Layer:

of

Cust. #:

Material:

8-GM-A

Appearance: white, nonfibrous, homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Asbestos Present: YES

Chrysotile - 5%

Other - 95%

Exterior Caulk, Paint Blue

On Mailboxes

NOT ANALYZED

Asbestos Present: NO

No Asbestos Observed

Asbestos Present:

Lab ID #: 75875 - 15

Ceramic Tile 4" White

Location: Debris Around Building

Robert T. Letarte Jr., Laboratory Director

Other - 100%

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Date Reported: 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 15a

Cust. #:

8-GM-A

Material:

Grout

Location: Debris Around Building

Appearance: grey,nonfibrous,homogenous

Layer:

75875 - 15b

Lab ID #: Cust. #:

8-GM-A

Material:

Mortar

Location: Debris Around Building

Appearance: beige, nonfibrous, homogenous

Layer: 3

of

Lab ID #: 75875 - 16

Cust. #:

8-GM-B

Material:

Ceramic Tile 4" White Location: Debris Around Building

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 16a

Cust. #:

8-GM-B

Material:

Grout

Location: Debris Around Building

Appearance: grey,nonfibrous,homogenous

Layer:

Lab ID #:

75875 - 16b

Cust. #:

8-GM-B

Material:

Mortar

Location: Debris Around Building

Appearance: beige, nonfibrous, homogenous

Layer: 3

of

Lab ID #: 75875 - 17

Cust. #:

9-BM-A

Material:

Brick Mortar

Location: Exterior, Exterior Brick

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 18

Cust. #:

9-BM-B

Material:

**Brick Mortar** 

Location: Exterior, Exterior Brick

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 19

Cust. #:

10-BM-A

Material:

**Brick Mortar** 

Location: Interior, Basements

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75875 - 20

Cust. #:

10-BM-B

Material:

**Brick Mortar** 

Location: Interior, Basements

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 21

Cust. #:

11-CC-A

Material:

Concrete Chip

Location: Poured Walls, Interior Basement Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 21a

Cust. #:

11-CC-A

Material:

Concrete

Location: Poured Walls, Interior Basement

Appearance: grey,nonfibrous,homogenous

Layer: 2 of

Lab ID #: 75875 - 22

Cust. #:

11-CC-B

Material:

Concrete Chip

Location: Poured Walls, Interior Basement Appearance: grey,nonfibrous,homogenous

Layer:

of

Asbestos Present: NO No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Cellulose - 50%

Other - 50%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 23

Cust. #:

12-CC-A

Material:

Concrete Chip

Location: Floor, Interior Basement Floor

Appearance: grey,nonfibrous,homogenous

Layer:

of

75875 - 24

Lab ID #: Cust. #:

12-CC-B

Material:

Concrete Chip

Location: Floor, Interior Basement Floor

Appearance: grey,nonfibrous,homogenous Layer:

of

Lab ID #: 75875 - 25

Cust. #:

13-VP-A

Material:

Vapor Paper

Location: Under Floors

Appearance: black, fibrous, homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #: Cust. #:

75875 - 26 13-VP-B

Material:

Vapor Paper

Location: Under Floors

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75875 - 27

Cust. #:

14-GM-A

Material:

Ceramic Tile 4" Blue Grey

Location: Bathroom Walls

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75875 - 27a

Cust. #:

14-GM-A

Material:

Grout

Location: Bathroom Walls

Appearance: grey,nonfibrous,homogenous

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Cellulose - 50%

Other - 50%

Asbestos Present: NO No Asbestos Observed

Other - 100%

Other - 100%

Asbestos Present: NO

No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 27b

Cust. #:

14-GM-A

Material:

Mortar

Location: Bathroom Walls

Appearance: white, nonfibrous, homogenous

Layer:

Lab ID #:

75875 - 28

Cust. #:

14-GM-B

Material:

Ceramic Tile 4" Blue Grey

Location: Bathroom Walls

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #: 75875 - 28a

Cust. #:

14-GM-B

Material:

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Other - 100%

Asbestos Present: NO No Asbestos Observed

Grout/Mortar

Location: Bathroom Walls

Appearance: grey,nonfibrous,homogenous

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director



#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 29 15-GM-A

Cust. #:

Ceramic Tile 1"x1" Blue Grey

Material:

Location: Bathroom Floors

Appearance: white, nonfibrous, homogenous

Layer:

75875 - 29a

Lab ID #: Cust. #:

15-GM-A

Material:

Grout/Mortar

Location: Bathroom Floors

Appearance: grey,nonfibrous,homogenous

Layer: 2

of

Lab ID #: 75875 - 30

Cust. #:

15-GM-B

Material:

Ceramic Tile 1"x1" Blue Grey

Location: Bathroom Floors

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18 03/28/18

Date Analyzed: Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 30a

Cust. #:

15-GM-B

Material:

Grout/Mortar

Location: Bathroom Floors

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 31

Cust. #:

16-CC-A

Material:

Concrete Chip

Location: Window Sills

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75875 - 32

Cust. #:

16-CC-B

Material:

Concrete Chip

Location: Window Sills

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 33

Cust. #:

17-WBS-A

Material:

Wallboard/Drywall

Location:

Throughout Buildings in Group 1

Appearance: white, fibrous, nonhomogenous

Layer:

of

Lab ID #:

75875 - 33a

Cust. #:

17-WBS-A

Material:

Joint Compound

Location: Throughout Buildings in Group 1

Appearance: beige, nonfibrous, homogenous Layer:

of

Lab ID #: 75875 - 34

Cust. #:

17-WBS-B

Material:

Wallboard/Drywall

Location: Throughout Buildings in Group 1 Appearance: white, fibrous, nonhomogenous

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Cellulose - 15%

Other - 85%

Asbestos Present: NO No Asbestos Observed

Other - 100%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 15% Other - 85%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported: 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 34a

Cust. #:

17-WBS-B

Material:

Joint Compound

Location:

Throughout Buildings in Group 1 Appearance: beige, nonfibrous, homogenous

Layer:

of

Lab ID #:

75875 - 35

Cust. #:

17-WBS-C

Material:

Wallboard/Drywall

Location: Throughout Buildings in Group 1 Appearance: white, fibrous, nonhomogenous

Layer:

of

Lab ID #: 75875 - 35a

Cust. #:

17-WBS-C

Material:

Joint Compound

Throughout Buildings in Group 1 Appearance: beige, nonfibrous, homogenous

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO No Asbestos Observed

Other - 85%

Cellulose - 15%

Other - 100%

Asbestos Present: NO

No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed:

Cellulose - 75%

Cellulose - 75%

Cellulose - 75%

Other - 25%

Other - 25%

Other - 25%

03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75875 - 36 18-BI-A

Material:

Blown In Insulation, Brown

Location: Exterior Walls

Appearance: brown, fibrous, nonhomogenous

Layer:

Lab ID #:

75875 - 37

Cust. #:

18-BI-B

Material:

Blown In Insulation, Brown

Location: Exterior Walls

Appearance: brown, fibrous, nonhomogenous

Layer:

of

Lab ID #: 75875 - 38

Cust. #:

18-BI-C

Material:

Blown In Insulation, Brown

Location: Exterior Walls

Appearance: brown,fibrous,nonhomogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 90%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: YES

Chrysotile - 10%

Non-Asbestos Material

Lab ID #:

75875 - 39

Cust. #:

19-WG-A

Material:

Window Glaze

Location:

Interior Fire Door w/ Reinforced Glass

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75875 - 40

Cust. #:

19-WG-B

Material:

Window Glaze

Location:

Interior Fire Door w/ Reinforced Glass

NOT ANALYZED

Asbestos Present: NO

No Asbestos Observed

Asbestos Present:

Appearance:

Layer:

Lab ID #:

75875 - 41

of

Cust. #:

20-WG-A

Material:

Window Glaze

Location: Stairwell Windows, Tilt In

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

Other - 100%

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 42

Cust. #:

20-WG-B

Material:

Window Glaze

Location: Stairwell Windows, Tilt In Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75875 - 43

Cust. #:

21-EC-A

Material:

**Exterior Caulk** 

Location: Along Roof Board

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #: 75875 - 44

Cust. #:

21-EC-B

Material: Exterior Caulk

Location: Along Roof Board

Appearance: white, nonfibrous, homogenous Layer:

of

Asbestos Present: NO

No Asbestos Observed

Asbestos Present: NO No Asbestos Observed

Asbestos Present: NO No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 45

Cust. #:

22-CA-A

Material:

Construction Adhesive

Location: Bathroom Sinks

Appearance: yellow,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 46

Cust. #:

22-CA-B

Material:

Construction Adhesive

Location: Bathroom Sinks

Appearance: yellow,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 47

Cust. #: Material: 23-SC-A Stack Cement

Location:

Appearance: white, fibrous, nonhomogenous

Laver:

of

Asbestos Present: **YES** 

Chrysotile - 10%

Other - 90%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To: Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present:

Asbestos Present:

NOT ANALYZED

Asbestos Present: NO

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75875 - 48

Cust. #: Material: 23-SC-B

Location:

Stack Cement

NOT ANALYZED

Appearance:

Layer:

Lab ID #:

75875 - 49

Cust. #:

23-SC-C

of

Material:

Stack Cement

Location:

Appearance: Layer:

of

Lab ID #:

75875 - 50

Cust. #:

24-CA-A

Material:

Construction Adhesive

Location: Kitchen Counters

Appearance: yellow,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

Other - 100%

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 51

Cust. #:

24-CA-B

Material:

Construction Adhesive

Location: Kitchen Counters Appearance: yellow,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 52

Cust. #:

25-FT-A

Material:

Floor Tile 9"x9" Green

Location: FS 445 West End

Appearance: green, fibrous, homogenous

Layer: 1 of

Lab ID #: 75875 - 52a

Cust. #:

25-FT-A

Material:

Mastic

Location: FS 445 West End

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Other - 90%

Chrysotile - 10%

Asbestos Present: YES

Asbestos Present: NO

No Asbestos Observed

Appearance: brown,nonfibrous,homogenous

Layer: 2

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75875 - 53

Cust. #:

25-FT-B

Material:

Floor Tile 9"x9" Green

Location: FS 445 West End

Appearance:

Layer:

Lab ID #:

75875 - 54

Cust. #:

26-FS-A

Material:

Floor Sheeting, Red Location: FS 445 Storage Closet 43

Appearance: black, fibrous, nonhomogenous

Layer: 1 of

Lab ID #: 75875 - 55

Cust. #:

26-FS-B

Material: Floor Sheeting, Red

Location: FS 445 Storage Closet 43

Layer:

of

Asbestos Present:

NOT ANALYZED

Asbestos Present: NO

No Asbestos Observed

Other - 60%

Cellulose - 40%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 40% Other - 60%

Appearance: black, fibrous, nonhomogenous

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75875

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **YES** 

No Asbestos Observed

No Asbestos Observed

Lab ID #:

75875 - 56

Cust. #:

27-BM-A

Material:

Brick Mortar, Black Mastic

Location:

Basements

Appearance: black,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 57

Cust. #:

27-BM-B

Material:

Brick Mortar, Black Mastic

Location: Basements

Appearance: black,nonfibrous,homogenous

Layer:

of

Lab ID #:

75875 - 58

Cust. #:

28-FD-A

Material:

Fire Door

Location:

Appearance: grey,fibrous,nonhomogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Non-Asbestos Material

Other - 100%

Other - 100%

Amosite - 45%

Other - 30%

Fiberglass - 25%

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



18-75875

03/23/18

ARI Report #

Date Collected:

Project: 810 S. Ballenger Highway- Group 1 Project #:188BS18146

46555 Humboldt, Ste. 100 Novi, MI 48377		Date Analyzed: 03/28/18 Date Reported: 03/28/18
Sample Information	Asbestos Type/Percent	Non-Asbestos Material
Lab ID #: 75875 - 59 Cust. #: 28-FD-B	Asbestos Present:	
Material: Fire Door Location: Appearance: Layer: of	NOT ANALYZED	
Lab ID #: Cust. #: Material: Location: Appearance: Layer: of	Asbestos Present:	
Lab ID #: Cust. #: Material: Location: Appearance: Layer: of	Asbestos Present:	

Robert T. Letarte Jr., Laboratory Director

Test Method EPA 600/R-93/116 was used to analyze the above samples. Matrix interference and/or resolution limits may yield false/negative results in certain circumstances. Suspect floor tiles containing <1% should be tested with SEM or TEM. This certificate of analysis relates only to the samples tested and to insure the integrity of the results, may only be reproduced in full. This certificate must not be used by the customer to claim product certification, approval, or endorsement by NVLAP, NIST, or any agency of the US Government. APEX Research Inc. is not responsible for the accuracy of the results for layered samples or samples comprising multiple materials. Liability limited to cost of analysis.




For Layered Samples, each component will be analyzed and reported separately.

Report To:

Mr. Rob Smith

#### Apex Research, Inc.

11054 Hi Tech Drive, Whitmore Lake, MI 48189. Phone: (734) 449-9990, Fax: (734) 449-9991.





3Client Name:	ATC Group Services	Date of Survey: <u>3-23-2018</u> .	good Suise
Address:	46555 Humboldt Drive, Suite 100	Project: 810 S. Ballenger Highway-Group1 .	Relinquished By: Joseph Seibert
City, St., Zip:	Novi, MI 48377	Project #:188BS18146 .	Date: 3/26/18
Phone:	(248) 669-5140		Received By: ARECEIVED
Fax:	(248)-669-5147	Contact Person: Rob Smith	Date: MAR 2 7 2018
I uz.	(240)-009-314/		2000.00201212.000000.000000000000000000

Turn Around Time: (CircleOne)	Rush	24 Hour X	48 Hour	72 Hour	Other:	TTP (Test Till Positive)
Asbestos	Bul	k: <u>X</u>	Point Count_		PCM	

#### pecial InstructionSEX RESEARCH

- 1st Positive Stop;
- Composite all drywall/joint compound samples if any layer of system is greater than 5% asbestos;
- Point Count ALL PLASTER samples Trace to 3% asbestos content
- Point Count ALL SAMPLES Trace to 1% asbestos content

Lab ID #	Client ID#	Material	Location	Quantity	Area	Results
1,2	1-WG-A,B	Window glaze, Vertical/openable basement windows (15)	Exterior	240 LF		
3,4	2-WG-A,B	Window glaze, 2 pane small windows (45)	Exterior	360 LF		
5,6	3-VB-A,B	Vapor board,	Exterior walls			
7.8	4-EC-A,B	Exterior caulk, Dark gray	On all basement windows	700 LF		
9,0	5-EC-A,B	Exterior caulk, light gray	Used at expansion joint and brick cracks			
11,12	6-EC-A,B	Exterior caulk, light gray with sparkles	On wood around all windows and doors	150 openings		
13.14	7-EC-A,B	Exterior caulk, painted blue	On mailboxes			
5,16	8-GM-A,B	Ceramic tile grout and mortar, 4" white	Debris around building	100 SF		
7,10	9-BM-A,B	Brick mortar, exterior	Exterior brick			
1920	10-BM-A,B	Block mortar, interior	Basements			
21,22	11-CC-A,B	Concrete chip, poured walls	Interior basement			
23,24	12-CC-A,B	Concrete chip, floor	Interior basement floor			
29,26	, 13-VP-A,B	Vapor paper	Under floors			
27,28	14-GM- A,B	Ceramic tile grout and mortar, 4" blue gray	Bathroom walls			

# 75875

#### Apex Research, Inc.

11054 Hi Tech Drive, Whitmore Lake, MI 48189. Phone: (734) 449-9990, Fax: (734) 449-9991.



Web Site: http://apexresearch-inc.com

29,30 15-GM-A,B	Ceramic tile grout and mortar, 1"x1" blue gray	Bathroom floors				
31,32 16-CC-A,B	Concrete Chip,	Window sills	150 SF	-		
32-35 17-WBS-A,B,C	Wall-board system, tape and mud	Throughout buildings in group 1				
36-36 18-BI-A,B,C	Blown in insulation, brown	Exterior walls				
29 40 19-WG-A,B	Window glaze,	Interior fire door with reinforced glass				
4147 20-WG-A,B	Window glaze,	Stairwell windows, tilt in	72 LF			
43,44 21-EC-A,B	Exterior caulk,	Along roof board	1000 LF			
45,46 22-CA-A,B	Construction adhesive,	Bathroom sinks				
47-49 23-SC-A,B,C	Stack cement		20 SF			
50 S 24-CA-A,B	Construction adhesive	Kitchen counters				
52,43 25-FT-A,B	Floor tile, 9"x9" green	FS 445 west end	80 SF			
94,55 26-FS-A,B	Floor sheeting, red	FS 445 storage closet 43	40 SF			
56.57 27-BM-A,B	Brick mortar, black mastic	Basements				
5G,50 28-FD-A,B	Fire door		15 doors			

Relinquished By: Joseph Seibert

Date: 3/26/18

RECEIVED

Received By:

Date:

MAR 2 7 2018

\*\*\*Terms and conditions on reverse side

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

Cellulose - 30%

Cellulose - 30%

Cellulose - 40%

Other - 60%

Other - 70%

Other - 70%

Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75876 - 01 1-VB-A

Material:

Vapor Board

Location: Behind Exterior Brick

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75876 - 02

Cust. #:

1-VB-B

Material:

Vapor Board

Location: Behind Exterior Brick

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #: 75876 - 03

Cust. #:

2-VP-A

Material:

Vapor Paper

Location: Under Wood Floors

Appearance: black, fibrous, homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed:

Cellulose - 40%

Other - 60%

Other - 100%

Other - 100%

03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 04 2-VP-B

Cust. #:

Vapor Paper

Material:

Location: Under Wood Floors

Appearance: black, fibrous, homogenous

Layer:

Lab ID #:

75876 - 05

Cust. #:

3-WG-A

Material:

Window Glaze

Location: Aluminum Frame Windows

Appearance: grey,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75876 - 06

Cust. #:

3-WG-B

Material:

Window Glaze

Location: Aluminum Frame Windows

Appearance: grey,nonfibrous,homogenous

Layer:

1 of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 07

Cust. #:

4-WG-A

Material:

Window Glaze

Location: Basement Metal Old Windows Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 08

Cust. #:

4-WG-B

Material:

Window Glaze

Location: Basement Metal Old Windows

Appearance: beige, nonfibrous, homogenous Layer:

of

Lab ID #: 75876 - 09

Cust. #:

5-WG-A

Material:

Window Glaze

Layer:

Location: Basement Metal New Windows Appearance: white, nonfibrous, homogenous

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO No Asbestos Observed

Other - 100%

Other - 100%

Asbestos Present: NO

No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 95%

03/28/18

#### Sample Information

#### Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: **YES** 

Chrysotile - 5%

No Asbestos Observed

#### Non-Asbestos Material

Lab ID #: 75876 - 10

Cust. #: 5-WG-B

Material:

Window Glaze

Location: Basement Metal New Windows Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75876 - 11

Cust. #:

6-EC-A

Material:

Exterior Caulk, Doors

Location: Windows, Bsmt Windows, Mailboxes

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75876 - 12

Cust. #: Material: 6-EC-B

Exterior Caulk, Doors

Location:

Windows, Bsmt Windows, Mailboxes

NOT ANALYZED

Asbestos Present:

Appearance: Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 13

Cust. #:

7-EC-A

Material:

**Exterior Caulk** 

Location: Air Conditioning Units

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75876 - 14

Cust. #:

7-EC-B

Material:

**Exterior Caulk** 

Location: Air Conditioning Units

Appearance: white, nonfibrous, homogenous

Layer:

1 of

Lab ID #: 75876 - 15

Cust. #:

Material:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO

Asbestos Present: **NO** 

Chrysotile - <1%

No Asbestos Observed

Other - 100%

Other - >99%

8-WBS-A

Joint Compound Location: Throughout Buildings

Appearance: beige, fibrous, homogenous

Layer:

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: **NO** 

POINT COUNT RESULT

Chrysotile - 0.25%

Non-Asbestos Material

Lab ID #:

75876 - 15-pc

Cust. #:

8-WBS-A

Material:

Joint Compound

Location:

Throughout Buildings

Appearance: beige, fibrous, homogenous

Layer:

of

Asbestos Present: NO No Asbestos Observed

Asbestos Present: NO

No Asbestos Observed

Cellulose - 20% Other - 80%

Cellulose - 20%

Other - 80%

Other - 99.75%

Cust. #: Material:

Lab ID #:

75876 - 15a 8-WBS-A

Wallboard/Drywall

Location: Throughout Buildings Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75876 - 16

Cust. #:

8-WBS-B

Material:

Wallboard/Drywall Location: Throughout Buildings

Appearance: grey,fibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 16a

Cust. #:

8-WBS-B

Material:

Joint Compound

Location:

Throughout Buildings Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75876 - 16a-pc

Cust. #:

8-WBS-B

Material:

Joint Compound

Location: Throughout Buildings

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #: 75876 - 17

Cust. #:

8-WBS-C

Material:

Wallboard/Drywall Location: Throughout Buildings

Appearance: grey,fibrous,homogenous

Layer:

of

Asbestos Present: NO

Chrysotile - <1%

Other ->99%

Other - 100%

Asbestos Present: NO Chrysotile - Trace

POINT COUNT RESULT

Asbestos Present: NO No Asbestos Observed

Cellulose - 20% Other - 80%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 17a

Cust. #:

8-WBS-C

Material:

Joint Compound

Location:

Throughout Buildings

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #:

75876 - 17a-pc

Cust. #:

8-WBS-C

Material:

Joint Compound

Location: Throughout Buildings

Appearance: beige, fibrous, homogenous

Layer:

of

Lab ID #: 75876 - 18

Cust. #:

9-SC-A

Material:

Stack Cement

Location: Chimney Stacks in Buildings Appearance: grey,nonfibrous,homogenous

Layer:

of

Asbestos Present: NO

Chrysotile - <1%

Other ->99%

Other - 99.50%

Asbestos Present: **NO** 

Chrysotile - 0.5%

POINT COUNT RESULT

Asbestos Present: NO

No Asbestos Observed

Other - 100%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 19

Cust. #:

9-SC-B

Material:

Stack Cement

Location: Chimney Stacks in Buildings

Appearance: black,nonfibrous,homogenous Layer:

of

Lab ID #:

75876 - 20

Cust. #:

9-SC-C

Material:

Mortar

Location: Chimney Stacks in Buildings

Layer:

of

Lab ID #: 75876 - 20

Cust. #:

Material:

Layer:

of

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Other - 100%

Other - 100%

Other - 100%

Appearance: grey,nonfibrous,homogenous

9-SC-C

Stack Cement

Location: Chimney Stacks in Buildings Appearance: black,nonfibrous,homogenous

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75876 - 21 9-SC-D

Material:

Stack Cement

Location: Chimney Stacks in Buildings Appearance: black,nonfibrous,homogenous

Layer:

Lab ID #:

75876 - 22

Cust. #:

9-SC-E

Material:

Stack Cement

Location: Chimney Stacks in Buildings Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75876 - 22a

Cust. #:

9-SC-E

Material:

Stack Cement

Location: Chimney Stacks in Buildings

Appearance: black,nonfibrous,homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 23

Cust. #:

10-EC-A

Material:

**Exterior Caulk** 

Appearance: white, nonfibrous, homogenous

Location: On Porch Metal Poles

Layer:

of

Lab ID #:

75876 - 24

Cust. #:

10-EC-B

Material:

**Exterior Caulk** 

Location: On Porch Metal Poles

Appearance: white, nonfibrous, homogenous

Layer:

1 of

Lab ID #: 75876 - 25

Cust. #:

11-BM-A

Material:

Brick Mortar

Location: Exterior

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: 75876 - 26

Cust. #: 11-BM-B

Material: **Brick Mortar** Location: Exterior

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 27

Cust. #:

12-CC-A

Material:

Concrete Chip

Location: Porches

Appearance: grey,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75876 - 28

Cust. #:

12-CC-B

Material:

Concrete Chip

Location: Porches

No Asbestos Observed

Appearance: grey,nonfibrous,homogenous

Layer: 1

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

Other - 100%

Other - 100%

Fiberglass - 80%

Other - 20%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 29

Cust. #:

13-CC-A

Material: Location: Concrete Chip Window Sills

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 30

Cust. #:

13-CC-B

Material:

Concrete Chip

Location: Window Sills

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75876 - 31

Cust. #:

14-FI-A

Material: Felt Insulation

Location: Air Conditioning Units

Appearance: black, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To: Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

Fiberglass - 90%

Other - 10%

Other - 100%

Other - 100%

03/28/18

Date Reported: 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 32 14-FI-B

Cust. #: Material:

Felt Insulation

Location: Air Conditioning Units Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75876 - 33

Cust. #:

15-IC-A

Material:

Interior Caulk

Location: Window Frames

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #: 75876 - 34

Cust. #:

15-IC-B

Material:

Interior Caulk

Location: Window Frames

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

Other - 100%

Other - 100%

Cellulose - 20%

Other - 80%

03/23/18 03/27/18

Date Analyzed: Date Reported:

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: 75876 - 35

16-IC-A

Cust. #:

Material: Interior Caulk

Location: Kitchen Cabinets

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #:

75876 - 36

Cust. #:

16-IC-B

Material:

Interior Caulk Location: Kitchen Cabinets

Appearance: white, nonfibrous, homogenous

Layer:

of

Lab ID #: 75876 - 37

Cust. #:

17-WB-A

Material:

Wallboard/Drywall

Location: Green Board in Basement of Unit 1

Appearance: grey,fibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Cellulose - 20%

Other - 80%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75876 - 38 17-WB-B

Material:

Wallboard/Drywall

Location: Green Board in Basement of Unit 1

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75876 - 39

Cust. #:

18-DG-A

Material:

Door Gasket

Location: FS 11

Appearance: brown,fibrous,nonhomogenous

Layer: 1

of

Lab ID #: 75876 - 40

Cust. #:

18-DG-B

Material:

Door Gasket

Location: FS 11

Appearance: brown,fibrous,nonhomogenous

Layer:

of

Asbestos Present: NO

No Asbestos Observed

Cellulose - 20% Other - 80%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 20% Other - 80%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Other - 100%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 41

Cust. #:

19-CC-A Concrete Chip

Material:

Location: Poured Walls

Appearance: grey,nonfibrous,homogenous

Layer:

of

75876 - 42

Lab ID #: Cust. #:

19-CC-B

Material:

Concrete Chip

Location: Poured Walls

Appearance: grey,nonfibrous,homogenous

Layer: 1

of

Lab ID #: 75876 - 43

Cust. #:

20-CC-A

Material:

Concrete Chip

Location: Basement Floors

Appearance: grey,nonfibrous,homogenous

Layer:

of

Asbestos Present: NO No Asbestos Observed

Other - 100%

Other - 100%

Asbestos Present: NO

No Asbestos Observed

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected: Date Received:

03/23/18 03/27/18

Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 44 20-CC-B

Cust. #: Material:

Concrete Chip

Location: Basement Floors

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 45

Cust. #:

21-WG-A

Material:

Window Glaze

Location: Egress Windows

Appearance: grey,fibrous,homogenous

Layer: 1

of

Cust. #:

Material:

Appearance: grey,fibrous,homogenous

Layer:

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO

Chrysotile - <1%

Other - >99%

Other - 100%

Lab ID #: 75876 - 45-pc

21-WG-A

Window Glaze

Location: Egress Windows

of

POINT COUNT RESULT

Asbestos Present: **NO** 

Chrysotile - Trace

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director



# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Chrysotile - <1%

Non-Asbestos Material

Lab ID #:

75876 - 46

Cust. #:

21-WG-B

Material:

Window Glaze

Location: Egress Windows

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #:

75876 - 46-pc

Cust. #:

21-WG-B

Material:

Window Glaze

Location: Egress Windows

Appearance: grey,fibrous,homogenous

Layer:

of

Lab ID #: 75876 - 47

Cust. #:

22-CT-A

Material:

Ceiling Tile, 12" Smooth

For Layered Samples, each component will be analyzed and reported separately.

Location:

Appearance: brown, fibrous, homogenous

Layer:

of

Asbestos Present: NO Other ->99%

Chrysotile - Trace

POINT COUNT RESULT

Asbestos Present: NO

Asbestos Present: NO No Asbestos Observed

Cellulose - 80% Other - 20%

Other - 100%

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #: Cust. #:

75876 - 48 22-CT-B

Material:

Ceiling Tile, 12" Smooth

Location:

Appearance: brown,fibrous,homogenous

Layer:

Lab ID #:

75876 - 49

Cust. #:

23-TU-A

Material:

**Tub Undercoating** 

Location: Bathrooms

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #:

75876 - 50

Cust. #:

23-TU-B

Material:

**Tub Undercoating** 

Location:

Bathrooms

Appearance:

Layer:

of

Asbestos Present: NO No Asbestos Observed

Cellulose - 80%

Other - 20%

Asbestos Present: YES

Chrysotile - 5%

Other - 95%

Asbestos Present:

NOT ANALYZED

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

 Report To:
 ARI Report #
 18-75876

 Mr. Rob Smith
 Date Collected:
 03/23/18

 ATC Group Services, LLC
 Date Received:
 03/27/18

 46555 Humboldt, Ste. 100
 Date Analyzed:
 03/28/18

 Novi, MI 48377
 Date Reported:
 03/28/18

Sample Information Asbestos Type/Percent Non-Asbestos Material

Lab ID #: 75876 - 51 Asbestos Present: **YES** Other - 40%

Cust. #: 24-DW-A Chrysotile - 60%

Material: Duct Wrap
Location: Basement of Unit 4

Appearance: grey,fibrous,homogenous

Layer: 1 of 1

of

Layer:

Lab ID #: 75876 - 52 Asbestos Present:

Cust. #: 24-DW-B Material: Duct Wrap

Material: Duct Wrap
Location: Basement of Unit 4

NOT ANALYZED

Appearance:

Lab ID #: 75876 - 53 Asbestos Present:

Cust. #: 24-DW-C Material: Duct Wrap

Location: Basement of Unit 4 NOT ANALYZED

Appearance:
Layer: of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director



# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #: Cust. #:

75876 - 54 25-GM-A

Material:

Ceramic Tile 1"x1" Grey

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 54a

Cust. #:

25-GM-A

Material:

Grout/Mortar

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75876 - 55

Cust. #:

25-GM-B

Material:

Ceramic Tile 1"x1" Grey

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received:

03/27/18

Date Analyzed: Date Reported:

Other - 100%

Other - 100%

Other - 100%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **NO** 

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 55a

Cust. #:

25-GM-B

Material: Location:

Grout/Mortar **Bathrooms** 

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 56

Cust. #:

26-GM-A

Material:

Ceramic Tile Grout/Mortar, 4"x4" Grey

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #: 75876 - 57

Cust. #:

26-GM-B

Material:

Ceramic Tile Grout/Mortar, 4"x4" Grey

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Non-Asbestos Material

Lab ID #:

75876 - 57a

Cust. #:

26-GM-B

Material:

Ceramic Tile Grout/Mortar, 4"x4" Grey

Location: Bathrooms

Appearance: grey,nonfibrous,homogenous

Layer:

Lab ID #:

75876 - 58

Cust. #:

27-FS-A

Material:

Floor Sheeting, Beige w/ Tan Crackle

Location: FS 141

Appearance: grey,fibrous,homogenous

Layer: 1 of

Lab ID #: 75876 - 59

Cust. #:

27-FS-B

Material: Floor Sheeting, Beige w/ Tan Crackle

Location: FS 141

Appearance: grey,fibrous,homogenous

Layer: 1 of

Asbestos Present: NO

No Asbestos Observed

Other - 100%

Asbestos Present: NO

No Asbestos Observed

Cellulose - 10% Fiberglass - 10%

Other - 80%

Asbestos Present: **NO** 

No Asbestos Observed

Cellulose - 10% Fiberglass - 10%

Other - 80%

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18 03/28/18

Date Reported:

Other - 95%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: YES

Chrysotile - 5%

Non-Asbestos Material

Lab ID #:

75876 - 60

Cust. #:

28-WG-A

Material:

Window Glaze

Location:

Aluminum Window, Unit 16, 28

Appearance: grey,fibrous,homogenous Layer:

of

Lab ID #:

75876 - 61

Cust. #:

28-WG-B

Material:

Window Glaze

Location:

Aluminum Window, Unit 16, 28

NOT ANALYZED

Asbestos Present:

Asbestos Present: NO

No Asbestos Observed

Appearance:

Layer:

of

Lab ID #: 75876 - 62

Cust. #:

29-GM-A

Material:

Ceramic Tile 12"x12" Beige Grout

Location: FS 163, 164

Appearance: white, nonfibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

Other - 100%

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

Other - 100%

Other - 100%

Other - 100%

03/28/18

Date Reported:

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 62a

Cust. #: 29-GM-A Material:

Mortar

Location: FS 163, 164

Appearance: grey,nonfibrous,homogenous

Layer:

of

Lab ID #:

75876 - 63

Cust. #:

29-GM-B

Material:

Ceramic Tile 12"x12" Beige Grout/Plaster

Location: FS 163, 164 Appearance: white, nonfibrous, homogenous

Layer: 1 of

Lab ID #:

75876 - 63a

Cust. #:

29-GM-B

Material:

Mortar

Location: FS 163, 164

Appearance: grey,nonfibrous,homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

2 of

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18

Date Received: Date Analyzed: 03/27/18

Date Reported:

Other - 95%

Other - 95%

03/28/18 03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: YES

Asbestos Present: YES

Chrysotile - 5%

Chrysotile - 5%

Non-Asbestos Material

Lab ID #: Cust. #:

Material:

75876 - 64

30-FT-A

Floor Tile, 9"x9" Beige Wood Grain

Location: FS 196

Appearance: beige, fibrous, homogenous

Layer:

Lab ID #:

75876 - 64a

Cust. #:

30-FT-A

Material:

Mastic

Location: FS 196

Appearance: black, fibrous, homogenous

Layer: 2

of

Cust. #:

Lab ID #: 75876 - 65

Material:

30-FT-B

Location: FS 196

NOT ANALYZED

Asbestos Present:

Appearance: Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Floor Tile, 9"x9" Beige Wood Grain

Robert T. Letarte Jr., Laboratory Director

# Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Cellulose - 90%

Cellulose - 90%

Other - 10%

Other - 95%

Other - 10%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present: NO

Asbestos Present: NO

Asbestos Present: **YES** 

Chrysotile - 5%

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 66 31-CP-A

Cust. #: Material:

Ceiling Panel, 18"x3' Smooth

Location: FS 196

Appearance: brown,fibrous,homogenous

Layer:

of

Lab ID #:

75876 - 67

Cust. #:

31-CP-B

Material:

Ceiling Panel, 18"x3' Smooth

Location: FS 196

Appearance: brown,fibrous,homogenous

Layer: 1 of

Lab ID #: 75876 - 68

Cust. #:

32-BM-A

Material:

Black Mastic

Location: All Basements

Appearance: black, fibrous, homogenous

Layer:

of

For Layered Samples, each component will be analyzed and reported separately.

Robert T. Letarte Jr., Laboratory Director

#### Test Method, Polarized Light Microscopy (PLM)



Project: 810 S. Ballenger Highway- Group 3 Project #:188BS18146

Report To:

Mr. Rob Smith

ATC Group Services, LLC 46555 Humboldt, Ste. 100

Novi, MI 48377

ARI Report #

18-75876

Date Collected:

03/23/18 03/27/18

Date Received: Date Analyzed:

03/28/18

Date Reported:

Cellulose - 60%

Cellulose - 60%

Other - 40%

Other - 40%

03/28/18

Sample Information

Asbestos Type/Percent

Asbestos Present:

NOT ANALYZED

Asbestos Present: NO

Asbestos Present: NO

No Asbestos Observed

No Asbestos Observed

Non-Asbestos Material

Lab ID #:

75876 - 69

Cust. #:

32-BM-B

Material:

**Black Mastic** 

Location: All Basements

Appearance: Layer:

of

Lab ID #:

75876 - 70

Cust. #:

31-VP-A

Material:

Vapor Paper Location: Exterior Wall, FS 117

Appearance: black, fibrous, homogenous

Layer:

of

Lab ID #: 75876 - 71

Cust. #:

31-VP-B

Material:

Vapor Paper

Location: Exterior Wall, FS 117

Appearance: black, fibrous, homogenous

For Layered Samples, each component will be analyzed and reported separately.

Layer:

of

Robert T. Letarte Jr., Laboratory Director

#### Apex Research, Inc.

1054 Hi Tech Drive, Whitmore Lake, MI 48189. Phone: (734) 449-9990, Fax: (734) 449-9991.



Web Site: http://apexresearch-inc.com

3Client Name:	ATC Group Services	Date of Survey: 3-23-2018 .	Joseph Substitution of the Contract of the Con
Address:	46555 Humboldt Drive, Suite 100	Project: 810 S. Ballenger Highway-Group3 .	Relinquished By: Joseph Seibert
City, St., Zip:	Novi, MI 48377	Project #:188BS18146 .	Date: 3/26/18
Phone:	(248) 669-5140		Received By: And Soli
Fax:	(248)-669-5147	Contact Person: Rob Smith	Date:
T ax.	(240)-009-514/		Special Instructions:

Turn Around Time: (CircleOne)	Rush	24 Hour X	48 Hour	72 Hour	Other:		TTP (Test Till Positive)	1st Positive Stop;     Composite all drywall/joint compound samples if any layer of system is greater than 5% asbestos;
Asbestos	Bul	k: <u>X</u>	Point Count_			PCM		<ul> <li>Point Count ALL PLASTER samples         Trace to 3% asbestos content     </li> <li>Point Count ALL SAMPLES Trace to 1%         asbestos content     </li> </ul>

Lab ID #	Client ID#	Material	Location	Quantity	Area	Results
1,2	1-VB-A,B	Vapor Board	Behind exterior brick			
3,4	2-VP-A,B	Vapor paper	Under wood floors	16, 000 SF		
5.6	3-WG-A,B	Window glaze	Aluminum frame windows			
7,8	4-WG-A,B	Window glaze	Basement metal old windows	600 LF		
9,10	5-WG-A,B	Window glaze	Basement metal new windows	400 LF		
11,12	6-EC-A,B	Exterior Caulk	Doors, windows, basement windows, mailboxes			
13,14	7-EC-A,B	Exterior Caulk	Air conditioning units	140 LF		
15-17	8-WBS-A,B,C	Wall-board system	Throughout the buildings			
18-2	⊋ 9-SC-A,B,€,Ď,E	Stack cement	Chimney stacks in the buildings	60 SF		
23,2	ب 10-EC-A,B	Exterior Caulk	On porch metal poles	30 LF		
252	6 11-BM-A,B	Brick mortar	Exterior			
27,	<u> 12-CC-A,B</u>	Concrete chip	Porches			
29,30	) 13-CC-A,B	Concrete chip	Window sills			
31,30	14-FI- A,B	Felt insulation	Air conditioning units	400 SF		



**Apex Research, Inc.**11054 Hi Tech Drive, Whitmore Lake, MI 48189. **Phone:** (734) 449-9990**, Fax:** (734) 449-9991.



Web Site: http://apexresearch-inc.com

		,. <b>.</b>	Sites http://aperhenearen inereem	
33,34	15-IC-A,B	Interior caulk	Window frames	
25,34	16-IC-A,B	Interior caulk	Kitchen cabinets	
47.30	17-WB-A,B	Wall-board	Green board in basement of unit 1	20 SF
39,40	18-DG-A,B	Door gasket	FS 11	20 LF
11142	19-CC-A,B	Concrete chip	Poured walls	
43,44	20-CC-A,B	Concrete chip	Basement floors	12,000 SF
N5,46	21-WG-A,B	Window glaze	Egress windows	60 LF
47,48		Ceiling tile, 12" smooth		
49,50	23-TU-A,B	Tub undercoating	Bathrooms	150 SF
51-53	24-DW-A,B,C	Duct wrap	Basement of unit 4	1 SF
54,55	25-GM-A,B	Ceramic tile grout and mortar, 1"x1" gray	Bathrooms	
56,57	26-GM-A,B	Ceramic tile grout and mortar, 4"x4" gray	Bathrooms	
25,59	27-FS-A,B	Floor sheeting, Beige with tan crackle	FS 141	60 SF
60,6	28-WG-A,B	Window glaze	Aluminum window, unit 16 and 28	120 LF
62,63	29-GM-A,B	Ceramic tile grout and mortar, 12"x12" Beige	FS 163, 164	120 SF
64,65	30-FT-A,B	Floor tile, 9"x9" beige wood grain	FS 196	60 SF
bb 67	31-CP-A,B	Ceiling panel, 18"x3' smooth	FS 196	80 SF
68,69	32-BM-A,B	Black mastic	All basements	
70,71	31-VP-A,B	Vapor Paper	Exterior wall, FS 117	100 SF

Relinquished By: Joseph Seibert

Date: 3/26/18

Received By:

Date:

\*\*\*Terms and conditions on reverse side.

# 810 S. Ballenger Hwy

# APPENDIX B QUALIFICATIONS



# United States Department of Commerce National Institute of Standards and Technology



# Certificate of Accreditation to ISO/IEC 17025:2005

**NVLAP LAB CODE: 102118-0** 

Apex Research, Inc.

Whitmore Lake, MI

is accredited by the National Voluntary Laboratory Accreditation Program for specific services, listed on the Scope of Accreditation, for:

# **Asbestos Fiber Analysis**

This laboratory is accredited in accordance with the recognized International Standard ISO/IEC 17025:2005.


This accreditation demonstrates technical competence for a defined scope and the operation of a laboratory quality management system (refer to joint ISO-ILAC-IAF Communique dated January 2009).

2017-10-01 through 2018-09-30

Effective Dates



For the National Voluntary Laboratory Accreditation Program





#### SCOPE OF ACCREDITATION TO ISO/IEC 17025:2005

#### Apex Research, Inc.

11054 Hi Tech Dr.
Whitmore Lake, MI 48189
Mr. Robert Letarte
Phone: 734-449-9990 Fax: 734-449-9991

Email: bletarte@apexmi.com http://www.apexmi.com

#### ASBESTOS FIBER ANALYSIS

#### **NVLAP LAB CODE 102118-0**

#### **Bulk Asbestos Analysis**

18/A03

<u>Code</u>	<u>Description</u>
18/A01	EPA Appendix E to Subpart E of Part 763 Interim Method of the Determination of Asbestos in

**Bulk Insulation Samples** 

EPA 600/R-93/116: Method for the Determination of Asbestos in Bulk Building Materials

For the National Voluntary Laboratory Accreditation Program

# **Asbestos Program**

**MIOSHA** 

(/AsbestosProgram/)

# Individual Profile for TINCU, BRANDEN C.

# Name and Address

#### Name

TINCU, BRANDEN C.

**Address** 

2025 BREWER ROAD HOWELL, MI 48855

# License Information

Accreditation Type: Contractor/Supervisor

ID#: A39513

Status: Apprvd - Full

**Expiration Date:** 4/3/2018

**Training Expiration Date:** 1/13/2018

**Accreditation Type:** Inspector

ID#: A39513

Status: Apprvd - Full

Expiration Date: 4/3/2018

**Training Expiration Date:** 10/14/2017

Q New Search (/AsbestosProgram/Individual/IndividualSearch)

<sup>\*</sup> Although this license may have been renewed, the new expiration date will not appear until the current one expires. Should you have questions, please call the Asbestos Program at 517-284-7680.

Back to Top MI.gov (http://www.michigan.gov)

Asbestos Program - Verify and Search (/AsbestosProgram/)

Asbestos Program (http://www.michigan.gov/lara/0,4601,7-154-11407 1533 15369---,00.html)

<u>Contact US (http://www.michigan.gov/lara/0,4601,7-154-11407 15333 15369-41708--,00.html)</u>

Policies (http://www.michigan.gov/policies)